




REV	DESCRIPTION	DATE	BY
P1	Making sketch for the prototype build plan	2026-10-02	AC



WHERE IT GOES
This part in colour, its neighbours in grey

HOW TO MAKE IT AND HOW IT FITS

Pipe lengths: 2,703 mm for the two posts on the right (low) side, 2,899 mm for the two on the left (high) side. Square cuts.

Cap plate 150 x 150 x 6 mm, two 11 mm holes 80 mm apart on the beam line. Weld it to the pipe top tilted 4 degrees, sloping down toward the right side, square to the beam.

Drill 13 mm through the pipe 50 mm above its foot; push a 200 mm length of 12 mm bar through and weld both sides (holds against uplift).

Paint the welds with zinc-rich paint.

Footing: hole 500 x 500 x 600 mm deep, centred 1,850 mm along and 1,400 mm across from the store centre (setting-out plan).

Stand the post 450 mm into the hole, plumb, plate tops on a string line: 2,253 mm above ground (right), 2,449 mm (left). Brace, pour.

Check: plumb both ways; plate tops within 5 mm of the line.

ZEERBOX

github.com/BoujeeEnjinia1701/zeerbox

ZeerBox roof post and footing (make 4): making sketch

DRAWING NO. ZBX-DWG-102			REV P1	SHEET 1 of 1	SIZE ANSI B
SCALE 1:25	UNITS mm	PROJECTION 	DATE 2026-10-02		DRAWN Amish Chadha
MATERIAL / NOTES Galvanized steel pipe 89 mm outside, 3 mm wall; 6 mm steel plate; 12 mm bar					
Licensed CERN-OHL-S-2.0 · Design Molecule Lab · designmolecule.com				Generated from cad/src; do not edit by hand	